

## **Microcomputer Triplex / Quadplex Relay**

# B

#### Operation

Initial application of power to the input terminals will flash the indicating LEDs for 2 seconds, but no loads will be energized. When #1 input switch closes, the appropriate load will be energized after 5 seconds. As additional input switches close, additional loads will be energized. The sequencing of the QPB becomes apparent when pump or pressure requirements are satisified and input switches begin to open.

If all input switches are closed and all loads are energized, when #4 input switch opens. #1 load de-energizes. The QPB sequences the loads, distributing the running time, using a First On First Off (FOFO) basis. If two or more loads are to be turned on simultaneously, the QPB will activate one load, and wait 5 seconds before turning on the next load. This staggered starting prevents line surges.

Any of the loads can be taken out of service or future expansion loads can be disabled by turning off the appropriate Relay Select switch(s). The QPB will sequence the remaining loads, skipping the disabled load(s).

The Alarm contact will activate whenever an input switch closes out of sequence. If #2 Input switch closes, but #1 remains open (because of a failure), the Alarm contact will close and the QPB will operate two pumps as if #1 Input switch had closed. When the condition indicating a fault clears, the Alarm resets automatically.

With two Relay Select switches disabled, the QPB performs a true duplex alternating operation, even if two loads are activated each time.

#### **Specifications**

Electrical Line Voltage: 24V AC/DC, ±10% 115 or 230VAC, ±10%, 1Ø, 50/60Hz Inputs: Normally Open (NO) contact or Solid State (NPN) Power Up Delay: 5 Sec., Fixed Input Delays: 5 Sec., Fixed **Output Ratings:** 10 Amps Total Unit Rating 5 Amps @ 240VAC, per contact 10 Amps @ 120VAC, per contact 100,000 Full Load Electrical Cycles 10,000,000 Mechanical Cycles Output Delays: 5 Sec., Fixed

Staggered start of multiple outputs

**Physical** 

Mounting: Surface Termination: Screw Terminals Removable (Plug-In) Packaging: Dust Cover Weight: 2 Lbs. Approx.

#### **Ambient Temperatures**

Operating: 0°C to 40°C Storage: -30°C to 85°C



- 4, 3 and 2 Pump Sequencing
- FOFO (First On / First Off)
- Removable Terminal **Blocks**
- Input De-Bounce Delay
- Staggered Starting
- Manual Output Select
- Alarm Output
- Indicating LEDs
- 10 Amp,1NO
- Pick-up Delays



#### Connections



3 Inputs Dry Contact Ø @@@@@ C 1 2 3 4 **Output Contact** c 1 2 3 4 A 구수수 0000000000  $\oslash$  $\oslash$ Load Voltage (L1) (L2) (L3) (L4)Â Alarm Voltage 115 VAC

### **Dimensions**







Microcomputer Triplex / Quadplex Relay



#### **Normal Operation**

For normal operation where four loads (pumps or compressors) are available, but only three Input Switches are closed at any one time. When Input Switch #1 closes, Load #1 energizes 5 seconds later. When Input Switch #2 closes, Load #2 energizes 5 seconds later. When Input Switch #3 closes, Load #3 energizes 5 seconds later. When Input Switch #3 is opened, the FOFO operation is observed. Since Load #1 was the first one on, then it is the first one off. When Input Switch #3 re-closes, Load #4 is the next one in sequence to energize. FOFO operation insures that all active outputs are operated in sequence and distributes



#### the running time between Loads. #3 Relay Select Disabled Operation

Where Load #3 (pump or compressor) has been taken out of service, but four Input Switches are still active. When Input Switch #1 closes, Load #1 energizes 5 seconds later. When Input Switch #2 closes, Load #2 energizes 5 seconds later. When Input Switch #3 closes, Load #4 energizes 5 seconds later since Load #3 has been disabled. When Input Switch #3 is opened, the FOFO operation is observed. Since Load #1 was the first one on, then it is the first one off. When Input Switch #3 re-closes, Load #1 now is the next one in sequence to energize. FOFO operation insures that all active Outputs are operated in sequence and distributes the running time between Loads.



#### **Engineering Specification Paragraph**

Logic controller must be able to operate as a 2, 3 or 4 pump (compressor) sequencer using a First On First Off (FOFO) operation, relative to the number of starters being used. Any combination or quantity of outputs may be disabled, maintaining the FOFO operation. Time delays of 5 seconds are required to de-bounce each input signal, in addition to a 5 second staggered start if more than one output is called into service at one time.

